



भारतीय प्रबंध संस्थान लखनऊ, नोएडा परिसर
Indian Institute of Management Lucknow, Noida Campus

Plot no. B-1, Sector -62 Institutional Area, Noida-201307, U.P
Tel: 0120-6678521/8426 Website: - www.iiml.ac.in
Email id: estateoffice_nc@iiml.ac.in

IIML-NC/RFQ/2026-27/003 Dated: 18/08/2026

REQUEST FOR QUOTATION

Dear Sir,

On behalf of the Director of Indian Institute of Management, Lucknow (IIML) you are hereby invited to quote your rates for "Reception Area Interior & branding work at IIM Lucknow(Noida Campus).", Plot no. B-1, Sector -62 Institutional Area, Noida-201307, U.P. as per details given below:

The work shall have to be completed within 15 DAYS from the date of award of work/letter of intent. The tender document should be signed in ink on each page of the tender, and any cutting or overwriting should accordingly be signed. All the papers should be submitted duly signed by the tenderer.

The condition of this notice and that mentioned in General Conditions, Special Conditions and BOQ enclosed will be binding on the tenderer. The Director, Indian Institute of Management, Lucknow reserves the right to reject one or all the tenders without assigning any reason. No claim, whatsoever, shall be entertained on this account.

The validity of the Quotation shall be 60 days from the date of opening of tenders. Tenders incorporating additional conditions are liable to be rejected.

Tenderers are advised to physically see the conditions of work and workplace before quoting. No deviation of rates or conditions of the contract will be accepted on account of ignorance of the workplace conditions after the award of the work. They are specifically advised to see the approachability of material and working conditions at the site.

Thanking you,

Yours faithfully,


Head Administration

- Encls:** 1. Instruction for Quotation: -
2. General Terms and Conditions
3. Special Conditions.
4. Bill of Quantity

INSTRUCTION FOR QUOTATION: -

Head Administration, Indian Institute of Management Lucknow, Noida Campus on behalf of Director, IIM Lucknow Noida campus invites request for quotation from Firms/ Contractors Registered in appropriate class as per details given below: -

- 1. Last date & time of submission of Quotation: - 25.08.2026 till 1200 hours**

BID SUBMISSION CHECK LIST

The sealed quotation (complete in all respect) must be submitted in tender box kept on ground floor of administrative block in **two separate sealed envelopes** as explained below: -

File – 1		
Sl. No.	Documents	Content
1	Technical Bid	Certificate of work experience of civil work amounting Rs 1,25,000/- in last 5 years.
2		Certificate of GST Registration.
		Average annual Turnover of Rs 1,25,000 in last three financial year ending 2025.(balance sheet /ITR copy)
3		Bidder shall sign all pages of the quotation document and attached the scanned copy of the same.
File – 2		
Sl. No.	TYPES	Content
1.	Financial Bid	Price bid should be submitted in signed BOQ format.

GENERAL TERMS AND CONDITIONS

1. **NAME OF WORK**

Reception Area Interior & branding work at IIM Lucknow (Noida Campus).

2. **SCOPE OF WORK**

1. Decorative wall paneling behind the reception counter.
2. Decorative Stainless Steel (PVD Gold Finish) metal inlay.
3. Decorative wooden fluted paneling/louvers.
4. Illuminated acrylic and stainless-steel IIM Lucknow logo signage.
5. Warm white LED strip lighting with aluminum
6. Replacement of damaged existing Gyproc false ceiling tiles.

3. **OWNER**

Indian institute of management Lucknow, Noida campus B-1, Sector -62 Institutional Area, Noida-201307, U.P.

4. **ENGINEER/ENGINEER-IN-CHARGE**

Competent Authority or any person designated from time to time by the owner and shall include those who are expressly authorized by him to act for and on his behalf for the operation of this contract.

5. **CONTRACT RATES**

The contract rates are for work to be done in IIML Noida Campus, and shall be firm throughout the currency of the contract including the extended period, if any, and shall not be subjected to any escalation due to any reason whatsoever it may be.

No escalation claim shall be entertained for any statutory increase by the Local Authorities or State/Central Government during the contract period.

The contract price shall be inclusive of the cost of all materials, labor, plants, and GST for the proper completion of jobs to the entire satisfaction of the owner and as per the technical specifications.

6. **COMMENCEMENT DATE**

The date of commencement of work shall be the date of issue of the Letter of Intent (LOI).

7. **PERIOD OF COMPLETION**

The period of completion shall be 15 working days from the date of L.O.I.

8. **PAYMENT TERMS**

The contractor may prepare and submit the bill based on the work completed and measured jointly by the IIML-NC engineer & contractor. 5% retention money will be deducted from each bill and shall be released after the completion of the defect liability period of 12 months. The vendor shall submit all documents required by the Accounts Department, such as the E-Way Bill, billing challan with matching HSN code, MTC and any other applicable documents, as per the requirement and applicability.

9. **TAX/DUTIES**

All taxes/duties, GST, or any other taxes or levies, etc. payable to any authorities whatsoever shall be borne by the contractor and the owner accepts no responsibilities or liability whatsoever on this account.

The rates shall remain firm and no enhancement/escalation on account of any statutory/other increases by Local Authorities, State/Central Government shall be entertained.

10. **TESTING OF MATERIALS**

Samples of various materials required for testing shall be provided free of charge by the Contractor. Testing charges if any shall be borne by the contractor. All other expenditures required to be incurred for taking the samples; conveyance, packing, etc. shall be borne by the contractor himself.

11. **AWARD OF WORK**

The firm qualifying technically & quoting the lowest rates shall be awarded the work.

12. **INSPECTION AND TESTING**

The IIML-NC or its authorized representatives shall have full power to inspect the work or examine the material. Acceptance of any material shall in no way relieve the contractor of his responsibility for meeting the requirements of the specifications. The contractor shall afford and procure for the owner every facility and assistance to carry out such inspection/tests. The cost of any special tests and/or analyses not called for in this specification shall be borne by the contractor. After completion of works, The work will be checked, and if any difference is found the same will be rectified by the contractor though it may require rework of any or all activity involved in the scope of work.

13. **LABOUR CAMP**

The contractors at their own risk and cost shall establish the Labor Camps outside the campus premises. No manpower of the contractor will be allowed to stay inside the complex. The contractor will have to make arrangements for staying/accommodation for his manpower outside the complex. Nothing extra shall be payable on this account.

14. **RETENTION MONEY:**

The 5% shall be deducted from each running account bill or final bill of the contractor as Retention Money. The 5% Retention Money shall be released to the contractor after the satisfactory completion of the Defect Liability Period of 12 months. If a successful tenderer fails to commence the work within 2 days from the date of issue of the Letter of Intent, the Institute may reject the award of work and get the work done by engaging another agency.

15. **SUB-STANDARD MATERIALS**

Any material rejected by the owner shall be removed from the site within 48 hours of the issue of instructions to this effect by the owner. Failing which, the IIML shall have to right to get these removed at the cost of the contractor and the contractor shall have no claim whatsoever in this regard.

16. **SPECIFICATION**

The contractor shall perform work in accordance with the latest CPWD Specifications and as per the direction of the Engineer in charge.

17. **DEFECT LIABILITY PERIOD**

12 months from the virtual date of completion.

18. **SECURED ADVANCE**

No secured advance shall be paid.

19. **CORRESPONDENCE**

All correspondence shall be addressed to:

Head Administration

First Floor, A1 Building.

Plot no. B-1, Sector -62 Institutional Area, Noida-201307, U.P.

20. **JURISDICTION**

The contractor shall be subject to the jurisdiction of the courts of Lucknow only.


 **Head Administration**

SPECIAL CONDITIONS

1. Where the work is found substandard the contractor shall be liable to rectify it to the satisfaction of Engineer-in-Charge by either rectifying or replacing.
2. All signatures in tender documents shall be dated as well as all the pages of all sections of the tender document shall be initiated at the lower right-hand corner and signed wherever required in the tender papers by the tenderer or by a person holding power of attorney authorizing him to sign on behalf of the tenderer before submission of tender.
3. No mobilization advance will be paid to the contractor.
4. If the altered/additional or substituted work or any additional work is required to be as per the IIML-NC requirement for which there are no established rates in BOQ and Delhi Schedule of Rates., the same shall be payable as per the provision stated hereunder.
5. If direct working out is not possible as mentioned in 4 & 5 above, the contractor shall be paid on the basis of the actual cost of material and labor cost plus 15% towards profit, supervision, overheads establishment, plants, machinery etc.
6. The rates quoted by the contractor and accepted by the Institute shall be firm and fixed for the above work and no escalation shall be paid to the contractor in this account.
7. In case the Institute is not satisfied with the performance of the contractor or the contractor delay the work, the Institute is empowered to get the work completed by another agency and debit the expenditure on the contractor's account. No objection or claim, whatsoever on this account will be entertained.
8. Rates given should be **inclusive of all Central, State, and Local taxes including Trade Tax on works contracts.**
9. Rates shall be deemed, inclusive of payments of dues by the contractor to the labour in accordance with the prevailing labour laws.
10. The work is to be executed in accordance with the latest Central Public Works Department (C.P.W.D.) specifications & contractor is required to follow all the applicable labour laws as specified in CPWD manual.
11. IIML-NC, reserves the right to curtail or enhance the scope of work either by deletion of certain items entirely or by reducing/increasing the quantities of certain items as required and reviewed by the Institute from time to time, and therefore, the final value of the work shall be worked out and paid to the extent of work actually carried out.
12. In case of defective works the same shall be rectified by the Contractor at his cost.
13. IIM Lucknow, Noida Campus reserves the right to terminate the agreement even without giving notice in the event the performance of the contractor is not found satisfactory.
14. Income Tax as per the rules will be deducted from the bill and the amount so deducted will be credited to the Income Tax authorities and a certificate of the amount credited will be issued by the account section of IIM Lucknow, Noida Campus.




15. Prevailing Turnover Tax will be recovered as per Government rules if applicable.
16. The dispute, if any, will be referred to the Director, IIM and his decision will be final and binding.
17. All disputes arising out of the order will fall under the jurisdiction of Lucknow Court.
18. Prior intimation will have to be given to the Engineer In-charge/JE by the contractor if he proposes to work on Sundays or any other holidays. The additional cost of wages and any other cost by overtime or shift work shall be borne in full by the contractor.
19. The contractor/ firm/ company shall be responsible and shall bear all costs and losses if any institute assets/items/tanks/ property etc. are found damaged.
20. The site shall be handed over to the Institute in working condition after satisfactory completion of the work. The unserviceable material shall be removed from the site and disposed of at Junkyard.
21. The terms & conditions given in the quotation inviting notice are also part of the General Terms and Conditions.
22. All the conditions of GCC available on the IIML website will be applicable. Link <https://www.iiml.ac.in/sites/default/files/upload/tender/293037022gcc.pdf>
23. The contractor should strictly adhere all the safety rules and regulations. The contractor shall be required to provide necessary safety arrangements to avoid any accidents. He shall be solely responsible for any accidents and payment of any compensation related to such accidents.
24. The contractor shall indemnify and keep indemnified the Indian Institute of Management, Lucknow Noida Campus against payments to be made under and for the observance of the laws aforesaid and the C.P.W.D. Contractor's Labour Regulations without prejudice to his right to claim indemnity from his sub-contractors.
25. Tender terms & conditions also include GCC which is uploaded on the IIML website and also part of this contract and its terms and conditions shall be binding to both IIML and the successful Tenderer. So please read it properly. Link <https://www.iiml.ac.in/sites/default/files/upload/tender/293037022gcc.pdf>
26. Please follow the rules of the security department at the main gate and the workplace.
27. For any site work, the contractor will have to follow the working schedule as per the working/operation condition of the pumps as per the lifting/distribution timing as suggested by the Engineer in Charge. No compensation in this regard will be given.
28. 0.05% per day of contract value for delays up to 15 days. 0.10% per day of contract value for delay from 15-30 days and for delay beyond 30 days it will be 0.25 % of the contract Value per day. The total levy of this Liquidated damage shall not exceed more than 10% of the contract value.



In case the delay continues beyond 2 Months then the tender/ Contract will be automatically canceled. Under These circumstances, the EMD/Performance Security/Retention available with the Institute will be forfeited. The Agency will be debarred from Biding with IIM Lucknow and will be blacklisted for 2 Years.

29. The contractor shall be responsible for the acts and deeds of its staff. IIM Lucknow will in no way be responsible for violation of any applicable law, rules and/or other loss caused either by the contractor or its staff.
30. IIM Lucknow Noida Campus reserves its right to recover from periodical payments to be made to the Contractor, any loss or damage that may be caused to the equipment, machinery, building or any other property of IIM Lucknow by negligence or any other reason whatsoever by the Contractor.
31. The contractor shall be bound to maintain a service record of complaints received and attended by his staff. The Staff will be under the control and supervision of the Contractor including their performance and discipline.
32. The Contractor shall be responsible for complying with the provisions of all the applicable laws and other enactments and amendments made thereto, from time to time, and the labour laws as may be in force and applicable.
33. None of the staff of the contractor shall be liable to claim any sort of employment with IIM Lucknow Noida Campus.
34. The Contractor shall ensure that the workmen employed are medically fit and in sound mind and health.
35. The contractor would ensure that his staff must have Identity cards to enter the premises of the IIM Lucknow Noida Campus for due performance of duties.
36. IIM Lucknow Noida Campus expects the contractor to ensure that his staff should maintain courteous behaviour.
37. The contractor should ensure that his staff should not be under the influence of liquor or any other such substance while on duty and any damage caused by such of the contractor's employee will be borne by the contractor.


 **Head Administration**

FINANCIAL BID
(To be submitted in separate envelope)

BILL OF QUANTITY

Reception Area Interior & branding work at IIM Lucknow (Noida Campus)

Sl No	Description	Estimated Amount	Quoted Rate (% below/above) of Estimate Amount	Quoted Amount
1	Reception Area Interior & branding work at IIM Lucknow(Noida Campus).	Rs 3,03,160/-		

Please note: -

1. Any additional conditions will not be entertained.
2. The above rates are inclusive of all taxes, Cess, Duties as applicable. Nothing extra would be paid.
3. The quoted percentage rate will automatically apply on all line items.



Estimate for reception Area Interior & branding work at IIM Lucknow(Noida Campus)										
S.No.	DSR Ref No	Description of an item	Nos	Length (Mtr.)	Bredth (Mtr.)	Depth/Height (mtr.)	Quantity	Rate	Unit	Amount
1	9.169	Providing and fixing 19 mm thick both side balancing lamination factory pressed BWP grade marine ply as per IS : 710 of approved brand boxes,shelves,racks,almirah,cupboard and drawer etc. including necessary nails,screws etc. complete as per direction of Engineer-incharge								
			1	7.32		3.36	24.5952	2593.15	sqm	63779.04
2	MR	Decorative SS/PVD Gold Finish Metal Inlay – Providing and fixing Decorative Stainless Steel MetalInlay Strips (thick and thin) of approved width and thickness, finished in PVD Gold Mirror Finish, recessed and fixed flush within the laminate wall paneling, including cutting of grooves in plywood panels, fabrication, edge finishing, adhesive fixing, alignment, polishing, transportation, labour, scaffolding and all incidental works complete as per approved design and direction of Engineer-in-Charge. The rate shall include: • Stainless Steel Grade 304 • PVD Gold Mirror Finish • Groove cutting in paneling • Adhesive fixing • Joint treatmentProtection during installation • Final cleaning and polishing Complete in all respects.								
			1				8	1300	Nos.	10400
3	RA	Decorative Wooden Fluted Paneling / Louvers - Providing and fixing Decorative Stainless Steel Metal Inlay Strips of approved width and thickness, finished in PVD Gold Mirror Finish, recessed and fixed flush within the laminate wall paneling, including cutting of grooves in plywood panels, fabrication, edge finishing, adhesive fixing, alignment, polishing, transportation, labour, scaffolding and all incidental works complete as per approved design and direction of Engineer-in-Charge. The rate shall include: • Vertical decorative fluted profile • Edge finishing • Groove alignment • Complete fixing arrangement • Finishing & cleaning								
			1	7.32		3.36	24.5952	1249		30719.4
4	MR	Illuminated Acrylic & SS Logo Signage – (4x3.5) ft Providing, fabricating, supplying and fixing illuminated IIM Lucknow logo signage comprising CNC-cut acrylic letters/logo with SS 304 mirror/PVD gold finish border and backlit LED illumination, complete with aluminium backing frame, power supply, drivers, wiring, mounting hardware, testing, commissioning, transportation, labour and installation, as per approved artwork and direction of Engineer-in-Charge. The rate shall include: • CNC-cut logo elements • Premium acrylic face • SS 304 PVD Gold / Brushed SS edging • Backlit LED illumination • Concealed aluminium framework • LED driver and electrical connections • Mounting on decorative wall panel • Complete installation and testing								
			1				1	126000	job	126000
5	MR	Warm White LED Strip with Aluminium Profile -(Approx 32 rnft) Providing and fixing warm white LED strip lighting (3000K) in anodized aluminium profile with opal diffuser, complete with BIS-approved drivers, FRLS wiring, connectors, fixing accessories, testing and commissioning, installed within reception counter grooves and decorative recesses complete as per approved design and direction of Engineer-in-Charge The rate shall include.Warm White LED Strip (3000K) Aluminium Extrusion Profile Polycarbonate/Opal Diffuser LED Driver Wiring & Connectors B Installation Accessories Testing & Commissioning								
			1	32			32	687.5		22000

6	15.57	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.							
			1	2	4.5		9	56.35	507.15
7	26.22.1	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595 mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on interlocking metal T-Grid of hot dipped galvanised iron section of 0.33 mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600 mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6 mm thick with precut hole on both 25 mm flange to pierce into 12x50 mm or even bigger size dash fastener if require, fixed with Galvanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall S.S screws. The work shall be carried out as per specifications, drawing and as per direction of the Engineer-in-Charge. With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles							
			1	2	4.5		9	2207	19863
8	12.55.1	Providing & fixing false ceiling at all height including providing & fixing of framework made of special section, power pressed from M.S. sheets and galvanised with zinc coating of 120 gms/ sqm (both side inclusive) as per IS : 277 and consisting of angle cleat of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm c/c, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 mm long with 6 mm dia bolts, other flange of cleat fixed to the angle hangers of 25 x10 x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I channels 45 x15 x 0.90 mm running at the spacing of 1200 mm c/c, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5mm, at 450 mm c/c, shall be fixed in a direction perpendicular to G.I intermediate channel with connecting clip made out of 2.64 mm dia x 230 mm long G.I wire at every junction, including fixing perimeter channels 0.50 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/ partitions with the help of Rawl plugs at 450 mm centre, with 25 mm long dry wall screws @ 230 mm interval, including fixing of Calcium Silicate Board to ceiling section and perimeter channels with the help of dry wall screws of size 3.5 x25 mm at 230 mm c/c, including jointing & finishing to a flush finish of tapered and square edges of the board with recommended jointing compounds, jointing tapes, finishing with jointing compounds in three layers covering up to 150 mm on both sides of joints and two coats of primer suitable for boards, all as per manufacture's specification and also including the cost of making opening for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in charge but excluding the cost of painting with: 8 mm thick Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process.							
			1	4.33	3.65		15.8045	1572.3	24849.42
9	13.82.2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two Coats							
			1	4.27	4.867		20.78209	137.45	2856.498
10	13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete							
			1	4.27	3.28		14.0056	156.05	2185.574
								Total	303160.1
								Say	303160